BRUHAT BANGALORE MAHANAGARA PALIKE
YELAHANAKA DIVISION

Name of work:

Improvement to Roads, Drains and Other Developmental Works at 407,707,208 SFS, Major Akshay Girish Kumar Road, Yelahanka 4th & 5th Phase and Surrounding Areas in Ward No.01,03 & 04 Of Yelahanka Division Under Amruth Nagarothan Grants (Package-04).

EIRL

EIRL

BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA DIVISION

Name of the work: Improvement to Roads, Drains and Other Developmental Works at 407,707,208 SFS, Major Akshay Girish Kumar Road, Yelahanka 4th & 5th Phase and Surrounding Areas In Ward No.01,03 & 04 Of Yelahanka Division Under Amruth Nagarothan Grants (Package-04).

Contractor Name:- Mohan Kumar S.R , Sulikere, Kengereri hobli, Sulikere post, Bangalore-560060

Job code No:- 004-23-000002

EXTRA ITEM RATE LIST (EIRL)

Sl. No.	Item Of Work	Unit	Estimate QTY	Rate in Rs. Considering 2021-2022 PWD SR	Amount (Rs.)	Whether the item alternative in tender or additional items	Whether the extra item is included in sanctioned estimate	How the Cost is proposed to be met	Whether extra item is included in S.R	Remarks
Eirl-1	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge. * Polished Granite stone slab Black, Cherry Red, Brown, Cat Eye, River Pink or equivalent.	**Sqm**	919.44	3196.04	**2938551.80**	Additional Item	No	-	**Yes, PWD SR 2021-22, Volume- 02, Page No-63, Item No 9.24**	
Eirl-2	Providing and fixing Structural Steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.	**Kgs**	1499.87	105.39	**158068.46**	Additional Item	No	-	**Yes, PWD SR 2021-22, Volume- 02, Page No-75, Item No 11.2**	

No.	Item Of Work	Unit	Estimate QTY	Rate in Rs. Considering 2021-2022 PWD SR	Amount (Rs.)	Whether the item alternative in tender or additional items	Whether the extra item is included in sanctioned estimate	How the Cost is proposed to be met	Whether extra item is included in S.R	Remarks
Eirl-3	Providing & fixing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete as per design drawings (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required as per the direction of Engineer in charge. 0.63 mm thick with zinc coating not less than 275 g/ m².	Sqm	50.00	881.93	44092.78	Additional Item	No	-	Yes, PWD SR 2021-22, Volume- 02, Page No-21, Item No 7.1.1	
	Total EIRL Amount :-				**3140713.04**					

Percentage of Excess comparing to the Santioned Estimated Cost = 3140713.04 / 88222198.67 *100 = 3.56%

Consultants

Assistant Engineer
Ward No-01, 03, 04
BBMP-Bangalore

Assistant Executive Engineer
Yelahanka Division
BBMP-Bangalore

MOHAN KUMAR, CIVIL CONTRACTOR

Executive Engineer
Yelahanka Division
BBMP-Bangalore